


The remote control is delivered as an accessory for the ASM 182 TD+ and as standard for the ASM 192 T2D+.


The remote control is equipped with a magnet allowing the operator to place it on a metallic surface. The operator can read the helium signal and has access to control keys such as cycle command auto-calibration and auto-zero.

Remote control interface




- 1 Helium Signal digital display
- 2 Correction factor COR indicator
- **3** Zero function indicator
- 4 Inlet port pressure analog display5 Test cycle ON indicator
 - Test cycle ON indicator (ON when activated)
- 6 Cycle Start/stop control key
- 7 Calibration in progress indicator
- 8 Auto-calibration start control key

- 9 Helium signal analogic display
- **10** Test ON indicator
- 11 Sniffing test mode ON indicator
- **12** Inlet VENT ON indicator
- **13** Helium signal standard scale ON indicator
- 14 Helium signal Zero scale ON indicator
- 15 Zero ON/OFF control key



So the operator should choice its remote control in accordance of the operation unit chosen.



When the operator connects the remote control on the leak detector, the leak detector unit is automatically reprogrammed with the unit of the remote control. The remote control unit is memorized by the detector when the operator disconnects the remote control.

Use and display

The remote control:

■ allows to display leak measured value,

 \blacksquare allows to start/stop cycle, zero function and internal autocalibration,

■ allows to display status of the air inlet vent, sniffing test mode and external auto-calibration,

■ doesn't allow to adjust leak detector parameters.



Analog and
digital displaysOn remote control and control panel, the displayed values on
the analog and digital displays are exactly the same.

Basic operation of the leak detector C 60

To start/stopIn order to start/stop a cycle, operator can use either the
CYCLE control key on the control panel or remote control.


Display

The LED indicator is ON/OFF when the control key is activated/deactivated.

As soon as the detector is in test, the TEST indicator is ON.

🛿 Basic operation of the detector 🌉 C 60

Zero function



In order to start zero function, operator can use either the ZERO control key on the control panel or remote control.

Display

Two indicators are ON when the zero function is activated: \Rightarrow the ZERO indicator,

➡ the zero scale indicator.



Internal auto-calibration



In order to start an internal auto-calibration, operator can use either the AUTOCAL control key on the control panel or remote control.

Display

The LED indicator is ON when the control key is activated. The LED indicator is OFF at the end of the auto-calibration procedure.

😮 Calibration of the leak detector 📖 C 70

Air inlet vent Sniffing test mode


For these 2 functions, the remote control displays only their status: use the control panel in order to activate/deactivate them.

VENT

Display

Display

The LED indicator is ON/OFF when the function is activated/deactivated.



External auto-calibration The remote control displays only its status: use the control panel in order start/stop it.



The LED indicator is blinking when the external autocalibration is activated.

At the end of the auto-calibration procedure, the LED indicator is OFF and VAC/SNIF COR is ON.

😢 External autocalibration 🏢 C 90